



NOTES:

1. AT THE CONNECTION TO THE SEWER MAIN A MAIN DIA. X 6" TEE IS REQUIRED FOR NEW SEWER MAINS AND A ROMAC TAPPING TEE OR CORE DRILLED INSERT-A-TEE REQUIRED FOR AN EXISTING SEWER MAIN.
2. 2x4 PRESSURE TREATED MARKER POST SHALL BE PAINTED WHITE WITH BLACK LETTERS "SEWER LOT # INVERT DEPTH".
3. 12 GAUGE WIRE SHALL BE CONNECTED TO PIPE AT INVERT AND WRAPPED AROUND MARKER POST.
4. DETECTOR TAPE REQUIRED FROM SEWER MAIN TO MARKER POST.
5. TEST TEE SHALL BE INSTALLED AT THE SEWER MAIN WHEN A SIDE SEWER IS CONNECTED TO AN EXISTING SEWER MAIN.



APPROVED BY	L. OLIVE
DATE	07/31/2008
REF STAD SPEC	

**DEPARTMENT OF PUBLIC WORKS
STANDARD DETAIL**

SIDE SEWER STUB

STANDARD DETAIL
NUMBER

SS-090