



NOTES:

1. TRENCH BACKFILL SHALL BE:
 - * PAVED AREA: GRANULAR BACKFILL AS APPROVED BY LOCAL AGENCY, OR PER WSDOT 9-03.9(3), OR CDF, OR 5/8" MINUS CRUSHED SURFACING, OR APPROVED NATIVE MATERIAL COMPACTED TO 95% OF MAXIMUM DENSITY.
 - * UNPAVED AREA: SELECTED GRANULAR MATERIAL WITH MAXIMUM DIMENSION OF 6" PER WSDOT 9-03.15, COMPACTED TO 90% OF MAXIMUM DENSITY.
2. GRAVEL BACKFILL FOR PIPE ZONE BEDDING SHALL BE SELECTED GRANULAR MATERIAL PER WSDOT 9-03.12(3), WASHED SAND, OR APPROVED SUITABLE EXCAVATED MATERIAL WITH MAXIMUM DIMENSION OF 1-1/2" COMPACTED TO 95% OF MAXIMUM DENSITY BY APPROVED HAND-HELD TOOLS.
3. EXCAVATE FOR THE PIPE BELL TO ENSURE UNIFORM SUPPORT FOR THE PIPE BARREL.
4. UNPAVED AREA SHALL BE RESTORED WITH 4" TOP SOIL, FERTILIZER AND SEED, OR AS SPECIFIED. PAVEMENT RESTORATION SHALL BE DONE PER RIGHT-OF-WAY USE PERMIT, OR AS SPECIFIED.



APPROVED BY	L. OLIVE
DATE	07/31/2008
REF STAD SPEC	

DEPARTMENT OF PUBLIC WORKS
STANDARD DETAILS

TYPICAL TRENCH DETAIL

STANDARD DETAIL
NUMBER
W-270