# HALLER PARK PARKING LOT

# CONSTRUCTION SET


APRIL 27, 2015

# SHEET INDEX

SHEET NAME	SHEET #
COVER SHEET	1
GENERAL NOTES	2
PAVING AND HORIZONTAL CONTROL PLAN	3
EROSION CONTROL, GRADING, AND DRAINAGE PLAN	4
COX AVE DRAINAGE PLAN	5
LIGHTING AND ELECTRICAL PLAN	6
PLANTING PLAN	7
DETAILS	8
DETAILS	9











City of Arlington Officials

PUBLIC WORKS DIRECTOR

JAMES X. KELLY, P.E.

BARBARA TOLBERT

COUNCIL MEMBERS

JESICA STICKLES

CHRIS RAEZER

DEBORA NELSON

RANDY TENDERING

MARILYN OERTLE

RICHARD BUTNER

JAN SCHUETTE

- 2. PRIOR TO ANY CONSTRUCTION ACTIVITY, THE DEVELOPER/ CONTRACTOR SHALL ATTEND A PRECONSTRUCTION CONFERENCE WITH THE CITY. THE CONSTRUCTOR SHALL SCHEDULE THE PRE—CONSTRUCTION CONFERENCE BY CALLING (360) 403—3500. PRIOR TO SCHEDULING, THE CONTRACTOR MUST SUBMIT AND RECEIVE APPROVAL FOR THE TRAFFIC CONTROL PLAN, CITY PERMITS, TEMPORARY EROSION AND SEDIMENT CONTROL PLAN, PERFORMANCE BOND, COPY OF OTHER AGENCY PERMITS, A COPY OF THE CONTRACTOR'S LICENSE, AND PROOF OF INSURANCE COVERAGE.
- 3. A COPY OF THE APPROVED CONSTRUCTION PLANS MUST BE ON THE JOB SITE WHEN CONSTRUCTION IS IN PROGRESS.
- 4. ALL SITE WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PLANS. ANY DEVIATION FROM THE APPROVED PLANS WILL REQUIRE PRIOR APPROVAL FROM THE OWNER, THE CITY ENGINEER, AND OTHER APPROPRIATE PUBLIC AGENCIES.
- 5. ALL OF THE LOCATIONS OF THE EXISTING UTILITIES SHOWN IN THE PLANS HAVE BEEN ESTABLISHED BY FIELD SURVEY OR OBTAINED FROM AVAILABLE RECORDS AND SHALL THEREFORE BE CONSIDERED APPROXIMATE AND NOT NECESSARILY COMPLETE. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO INDEPENDENTLY VERIFY THE ACCURACY OF ALL UTILITY LOCATIONS.
- 6. THE CONTRACTOR SHALL LOCATE AND PROTECT ALL CASTINGS AND UTILITIES DURING CONSTRUCTION AND SHALL CONTACT THE UNDERGROUND UTILITIES LOCATE SERVICE (1-800-424-5555 OR 811) AT LEAST 48 HOURS PRIOR TO CONSTRUCTION.
- 7. INSPECTION AND ACCEPTANCE OF ALL WORK WILL BE ACCOMPLISHED BY REPRESENTATIVES OF THE CITY OF ARLINGTON. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE AND SCHEDULE APPROPRIATE INSPECTIONS, ALLOWING PROPER ADVANCE NOTICE. THE INSPECTOR MAY REQUIRE REMOVAL AND REPLACEMENT OF ITEMS THAT DO NOT MEET CITY STANDARDS OR WERE CONSTRUCTED WITHOUT INSPECTION.
- 8. THE CONTRACTOR SHALL KEEP THE ON-SITE AND OFF-SITE STREETS CLEAN AT ALL TIMES BY CLEANING WITH A SWEEPING AND/OR VACUUM TRUCK. WASHING OF THESE STREETS WILL NOT BE ALLOWED WITHOUT PRIOR APPROVAL FROM THE CITY INSPECTOR.
- 9. THE CONTRACTOR SHALL MAINTAIN TWO (1) SET OF "AS— BUILT" PLANS SHOWING ALL FIELD CHANGES AND MODIFICATIONS. IMMEDIATELY AFTER CONSTRUCTION COMPLETION, THE CONTRACTOR SHALL DELIVER THE COPY OF RED—LINED PLANS TO THE CITY.
- 10. CONTRACTOR SHALL REMOVE AND REPLACE EXISTING CONCRETE SIDEWALK AS NEEDED TO INSTALL NEW SERVICE CONNECTIONS. EXISTING SIDEWALKS ARE APPROXIMATELY 5-FT WIDE.
- 11. IN LANDSCAPE AREAS, CONTRACTOR SHALL RESTORE SITE WITH 2-IN LAYER OF 3-WAY COMPOST MATERIAL AND WSDOT STANDARD GRASS SEED MIX.
- 12. PAVEMENT RESTORATION SHALL BE PER CITY OF ARLINGTON DETAIL R-140.
- 13. DEMOLITION OF EXISTING SURFACE AND BELOW GRADE FEATURES SHALL BE DETERMINED BY EXTENT OF PROPOSED IMPROVEMENTS.

#### TESC NOTES

- 1. THE TESC BMP'S SHOWN ON THE PLAN MUST BE INSTALLED PRIOR TO ALL OTHER CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT—LADDEN WATER DOES NOT ENTER THE DRAINAGE SYSTEM, LEAVE THE SITE, OR VIOLATE APPLICABLE WATER QUALITY STANDARDS. MAINTENANCE, REPLACEMENT, AND UPGRADING OF THE TESC PLAN IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETE AND APPROVED BY THE CITY.
- 2. THE TESC FACILITIES SHOWN ON THE PLANS ARE THE MINIMUM REQUIREMENTS FOR THE ANTICIPATED SITE CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, THESE TESC FACILITIES SHALL BE UPGRADED AND ADDED TO AS NEEDED, FOR UNEXPECTED STORM EVENTS AND TO REFLECT CHANGED CONDITIONS, AS REQUIRED BY THE CITY.
- 3. THE CONTRACTOR SHALL PROVIDE THE CITY A 24-HOUR EMERGENCY CONTACT PHONE NUMBER OF THE CONTRACTOR'S CERTIFIED EROSION CONTROL SUPERVISOR PRIOR TO STARTING CONSTRUCTION.
- 4. THE TESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE CONTINUED FUNCTION AND OPERATION.
- 5. BETWEEN OCTOBER 1 AND APRIL 30, DISTURBED AREAS THAT ARE TO BE LEFT UNWORKED FOR MORE THAN TWO (2) DAYS SHALL BE IMMEDIATELY COVERED BY MULCH, SOD OR PLASTIC COVERING. BETWEEN MAY 1 AND SEPTEMBER 30, DISTURBED AREAS THAT ARE TO BE LEFT UNWORKED FOR MORE THAN SEVEN (7) DAYS SHALL BE IMMEDIATELY COVERED BY SEEDING OR OTHER APPROVED METHODS.
- 6. SEDIMENT DEPOSITS SHALL BE REMOVED FROM ALL CATCH BASINS, PRE-TREATMENT/SEDIMENT POND, AND SEDIMENT TRAPS UPON REACHING A DEPTH OF 12 INCHES.
- 7. INFILTRATION AREAS, SUCH AS RAIN GARDENS, SHALL BE PROTECTED FROM CONSTRUCTION TRAFFIC AND SILT LADEN RUNOFF.
- 8. WHERE STRAW MULCH FOR TEMPORARY EROSION CONTROL IS REQUIRED, IT SHALL BE APPLIED AT A MINIMUM THICKNESS OF 3 INCHES, OR 3,000 POUNDS PER ACRE.
- 9. SOIL STOCKPILES SHALL BE STABILIZED WITHIN 24 HOURS. WHEN ACTIVELY WORKING WITH THE SOIL STOCKPILE, STABILIZATION BY GROUND COVER BMPS SHALL OCCUR AT THE END OF EACH WORK DAY.
- 10. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT
- 11. MAINTENANCE AND REPAIR OF TESC FACILITIES AND STRUCTURES SHALL BE CONDUCTED IMMEDIATELY UPON RECOGNITION OF A PROBLEM OR WHEN THE TESC MEASURES BECOME DAMAGED.
- 12. UPON COMPLETION OF THE PROJECT, ALL BMP'S SHALL BE REMOVED FROM THE SITE AND RIGHT OF WAY. IF BMP'S ARE REQUIRED TO REMAIN IN PLACE FOR FURTHER PROTECTION, ARRANGEMENTS FOR REMOVAL SHALL BE MADE WITH THE CITY INSPECTOR.

#### STORM DRAIN NOTES

- 1. PIPE MATERIAL SHALL BE LINED CORRUGATED POLYETHYLENE PIPE (LCPE), IN ACCORDANCE WITH AASHTO M252 TYPE S.
- 2. PIPE BEDDING MATERIAL SHALL BE 3/8-INCH PEA GRAVEL
- 3. ALL TRENCH BACKFILL IN AREAS OF PAVEMENT OR STRUCTURAL LOADING SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY. ALL OTHER AREAS SHALL BE COMPACTED TO AT LEAST 90% OF MAXIMUM DRY DENSITY.
- 4. ALL PIPE SHALL BE PLACED ON STABLE EARTH. IF IN THE OPINION OF THE CITY INSPECTOR, THE EXISTING TRENCH FOUNDATION IS UNSATISFACTORY, THEN IT SHALL BE EXCAVATED BELOW GRADE AND BACKFILLED WITH GRAVEL BEDDING MATERIAL TO SUPPORT THE PIPE.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING ALL MANHOLE, INLET AND CATCH BASIN FRAMES AND GRATES/COVERS TO GRADE JUST PRIOR TO CURB INSTALLATION AND/PAVING.
- 6. STORM WATER RETENTION/DETENTION FACILITIES, STORM DRAINAGE PIPE AND CATCH BASINS SHALL BE FLUSHED AND CLEANED BY THE CONTRACTOR PRIOR TO THE CITY'S ACCEPTANCE OF THE PROJECT.
- 7. WHEN INFILTRATION FACILITIES ARE CONSTRUCTED, COMPACTION OF SOIL IS NOT ALLOWED, AS THE DESIGN IS BASED ON NATURAL SOIL IN THE ORIGINAL LOCATION. VEHICLES SHALL NOT BE DRIVEN OVER THE INFILTRATION AREA DURING CONSTRUCTION.
- 8. CONTRACTOR SHALL INCLUDE DEWATERING IN THEIR BID. BASIS OF BID SHALL ASSUME DEPTH TO GROUNDWATER IS 15'.

#### ADA NOTES


- 1. ALL ADA FACILITIES SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE PROPOSED RIGHT-OF-WAY ACCESSIBILITY GUIDELINES (PROWAG) GUIDELINES.
- 2. UNLESS OTHERWISE SPECIFIED ON THE PLANS, OR DIRECTED BY THE ENGINEER, CROSS SLOPES OF SIDEWALKS SHALL BE A NOMINAL 1.5%. CROSS SLOPES SHALL NOT BE LESS THAN 1% NOR EXCEED 2%.
- 3. MAXIMUM SLOPES SHOWN ON THE PLANS REPRESENT THE MAXIMUM ALLOWABLE SLOPES PERMITTED BY CURRENT ADA REQUIREMENTS. THE CONTRACTOR SHALL TAKE INTO CONSIDERATION CONSTRUCTION TOLERANCES WHEN PLACING SIDEWALKS TO INSURE MAXIMUM SLOPES ARE NOT EXCEEDED.
- 4. CONTRACTOR SHALL NOTIFY CITY OF ANY DISCREPANCIES BETWEEN ELEVATIONS AND/OR MEASUREMENTS SHOWN ON THE PLANS AND REQUIRED ADA STANARDS.
- 5. COMPLETED SIDEWALKS OR OTHER HARDSCAPE ELEMENTS THAT EXCEED MAXIMUM SPECIFIED SLOPES OR ARE LESS THAN MINIMUM SPECIFIED SLOPES SHALL BE REMOVED AND REPLACED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE.
- 6. MEASUREMENT OF SLOPES SHALL BE PERFORMED ON THE WALKABLE SURFACE AND SHALL NOT TAKE INTO CONSIDERATION THE CURB ELEVATION.
- 7. FORMWORK FOR CURBS, SIDEWALKS, RAMPS, AND DRIVEWAYS SHALL BE INSPECTED BY CITY PRIOR TO CONCRETE POUR TO INSURE COMPLIANCE WITH ADA STANDARDS.

### CONSTRUCTION SET

 PLAN CHECK
 BY
 DATE
 Image: Control of the property of

JAMES X. KELLY E
PUBLIC WORKS DIRECTOR

DATE APPROVED:



CITY OF ARLINGTON
DEPARTMENT OF
PUBLIC WORKS

FUNDING NO.  $\frac{P02.382}{}$ 


HALLER PARK PARKING LOT


GENERAL NOTES


REFERENCE SHEET NO.


C
SHEET


2 OF 9 SHEETS














JAMES X. KELLY

DATE NO.

E. SCOTT

**DESIGNED BY:** 

**REVISION** 

DRAWN BY:

E. SCOTT

BY

PUBLIC WORKS DIRECTOR

03-16-2015

DATE APPROVED:

CONSTRUCTION REFERENCE

TANDARD DETA NUMBER

SS-010

FACE OF CURB

CURB AND GUTTER SHOWN

OT INCLUDED IN BID ITEM

**SIDEWALK** 

SHEET 1 OF 1 SHEET

STATE DESIGN ENGINEER




**DEPARTMENT OF PUBLIC WORKS** 


FUNDING NO. <u>P02.382</u>


**DETAILS** 


SHEET NO SHEET OF


SHEETS























## CONSTRUCTION SET







CITY OF ARLINGTON
DEPARTMENT OF
PUBLIC WORKS

FUNDING NO. P02.382

# HALLER PARK PARKING LOT

DETAILS

REFERENCE SHEET NO. C SHEET 9 OF 9 SHEETS